

## CITY OF CHICAGO DEPARTMENT OF PUBLIC HEALTH UNDERGROUND STORAGE TANK UNIT 2160 W. OGDEN AVENUE CHICAGO, IL 60612

## REQUIRED CHECKLIST FOR UNDERGROUND STORAGE TANK INSTALLATION

UST installations shall follow 41 Ill Adm Code Part 174 and any referenced material. The following checklist shall be followed as prescribed by the Department of Public Health's regulations. These requirements do not exempt anyone from other State or Federal requirements or regulations. Underground Storage Tank or UST includes underground pipes and cathodic protection connected thereto.

A.	Secure proper permitting and required notices of installation to the CDPH. Part 175
B.	Conduct on-site inspection to ensure accuracy of approved blue prints, drawings and actual equipment being installed. Part 175
C.	Equipment with sufficient lifting capacity shall be used to unload and place USTs into the tank excavation. Tanks shall not be rolled, dropped or dragged. API 1615 3.4.1
D.	Upon delivery, at installation site, tanks and piping shall be inspected to detect any evidence of damage to coating or structure. API 1615 3.4.1
E.	Upon discovery of any damage to tanks or piping, repairs shall be in accordance with the manufacturer's instructions and/or supervision. API 1615 3.5.1.2
F.	Prepare excavations to ensure safe movement of equipment and materials. Excavations shall provide adequate space of the installation of tanks, piping and ancillary equipment. Special attention shall be given to sloping or shoring the sides of the excavation to make them stable. API 1615 5.1.2
S T O P!!!	
CDPH Tank Specialist must witness ALL testing of USTs before installation, the placement of USTs and all backfilling operations around the USTs. 425 ILCS 25/9	
G.	To prevent flotation of USTs, as a result of high water table or flooding, approved anchorage methods and/or ballasting shall be installed. API $1615\ 6.2$ - $6.4$
H.	Pipe trenches shall meet manufacturer's specifications and API 1616. Section 10.3.1, for depth, width, slope, spacing and placement of pipe within. API 1615 10.3.1
I.	Pipe installation shall meet manufacturer's specifications and API 1615 Section 9.3 and 9.4. Joint adhesive and thread sealant shall meet manufacturer's requirements for petroleum products and/or gasoline - ethanol and gasoline - methanol blends. API 1615 9.3 - 9.4
J.	Electrical conduit shall be routed away from product piping, and shall not be installed in the same trenches as product piping. PEI 100 section 11.1
STOP!!!	
DOE Tank Specialist must witness air test of pipe installation and backfilling of pipe trenches. 425 ILCS 25/9	
K.	Wiring of electrical pumps and all electrical equipment in connection therewith shall conform to Chapter 5 of the 1981 Edition of the National Electrical Code, NFPA #70.
L.	For all UST installations, the final inspection shall not be scheduled without prior submission of: The completed electronic Notification for Underground Storage Tanks the completed OSFM on-line forms for all required testing; and, if applicable, the completed motor fuel dispensing permit application. 170.420(e)(5)